

PUR805- City Hall Tree Replacement - Addendum and Alternate 1

- Add stepping stones under benches and planters color to match Plaza pavers.
- Remove and reinstall landscape lighting. One outlet and up-light per Linden tree.
- Irrigation plan to be approved by City Staff prior to installation
- Erosion control measures will be installed if needed by weather conditions.
- Contractor is responsible for all cones, barricades, flagging, caution tape, etc. needed to secure project area.
- The selected contractor should only repoint those areas in need of repair.
- The selected contractor should only use reddish tan concrete for the repointing.
- See attachment for uplighting specifications.

	Plant Plan	
Plant	Amount/Size	Instructions
Little Leaf Linden	5 – 3 to 3.5” caliper	See Drawing
Elm “Alee”	4 – 3 to 3.5” caliper	See Drawing
Trident Maple	2 – 3 to 3.5” caliper	See Drawing
Magnolia “Kay Parris”	1 – 30 gal/ 8 ft.	See Drawing
Crape Myrtle “Cherry Dazzle”	31 – 3 gal	See Drawing
Globe Cytomeria	36 – 3 gal	See Drawing
Pink Muhley	16 – 1 gal	See Drawing
White Muhley	28 – 1 gal	See Drawing
Daffodil bulbs	400	See Drawing
Purple Heart (setcreasea)	22 – 1 gal	See Drawing
Carex “Blue Zinger	100 - pint	See Drawing
Liriope “Gold Ingot”	300 - pint	See Drawing

Alternate 1:

Repointing of brick work at the upper terrace of City Hall amphitheater and the brickwork in front of the City Hall plaza. Work areas should include entire terrace and selected areas of the plaza. Entirety of both sites should be cleaned post construction.

A new bid form will be issued to include a space for a bid for this item.