

PUR806- Black St Column Repair- Addendum 1

- Carbon fiber sheets for Item 2 should be applied horizontally.
- All work for Item 2 should follow the revised Carl Walker diagram SR502.
- The revised diagram for Item 2 specifies that the wall should be covered on both sides with carbon fiber sheets. The stair side of the wall should be covered from the top of the wall down four vertical feet.
- If the work in Item 2 requires that the stairs be closed while work is being completed, the selected contractor should provide all proper signage. Only one stairway may be closed at a time. Stairs should only be closed during working hours. If the contractor deems that the stairs need to be closed overnight, advanced approval must be given by an authorized member of City staff before doing so.
- All scaffolding or other apparatus needed for applying the sheets to the stairway side of the wall should be provided by the contractor.
- The selected contractor should ensure that brick placement in Item 3 is performed on suitable foundation to prevent future settling and cracking. Any work should be coordinated with an authorized member of City staff before placing the brick.